Book 81 Page 72



VICINITY MAP
NOT TO SCALE

Review Officer's Certificate

State of North Carolina
County of ______________

I, ______________, Review Officer of ______________ County certify the map or plat to which this certification is affixed meets all statutory requirements

Date ______________ Review Officer

Surveyor's Certificate

I, PHILIP N. POST, certify that this plat was drawn under my supervision from an actual survey made under my supervision (deed description recorded in Book 1559, page 438); that the boundaries not surveyed are clearly indicated as dashed lines, drawn from information found in Book SEE, page REF; that the ratio of precision as calculated is 1: 10,000+ that this plat was prepared in accordance with G.S. 47-30 as amended. Witness my original signature, registration number and seal this 30th day of July, 1998.

Surveyor ______________

Registration Number L-2519

I hereby certify to one of the following:

___a. That this survey creates a subdivision of land within the area of a county or municipality that has an ordinance that regulates parcels of land.

___b. That this survey is located in such portion of a county or municipality that is unregulated as to an ordinance that regulates parcels of land.

_X_c. That this survey is of an existing parcel or parcels of land.

___d. That this survey is of another category, such as the recombination of existing parcels, a court ordered survey, or other exception to the definition of subdivision.

___e. That the information available to the surveyor is such that the surveyor is unable to make a determination to the best of his or her professional ability as to provisions contained in (a) through (d) above.

Surveyor ______________ 7-30-98 Date



REFERENCES:

FOR UNIVERSITY COMMONS:
DB 136, PG 162
PLAT 78-174
DB 1559, PG 438
DB 539, PG 353
PLAT 42-181
TAX REF: TM 7.122.B.1B (PIN ~~9778-71-7299~~)

FOR TAX PARCELS SHOWN:
DB 1333, PG 359
DB 1581, PG 291
DB 211, PG 512
DB 200, PG 863

LEGEND:

- EIP = EXISTING IRON PIPE
- EIR = EXISTING IRON ROD
- CON.MON. = EXISTING CONCRETE MONUMENT
- IRS = IRON ROD SET
- CP = COMPUTED POINT (NOTHING SET)
- FW — FLOODWAY LIMIT LINE
- FP — FLOODPLAIN FRINGE LIMIT LINE
- CARRBORO & CHAPEL HILL TOWN BOUNDARY LINE

LINE TABLE:

LINE	DIRECTION	DISTANCE
L02	N 56°08'28" E	78.94'
L03	N 68°36'46" W	44.97'
L04	N 21°20'59" E	60.00'
L05	S 68°36'46" E	45.01'
L06	S 29°45'50" E	103.86'
L07	N 09°34'36" W	69.58'
L08	S 63°09'19" E	10.00'
L09	N 60°14'10" E	143.47'
L10	N 72°15'07" E	79.73'
L11	S 83°39'37" E	91.58'
L12	N 06°41'17" W	110.92'
L13	N 83°18'43" E	26.09'
L14	N 06°41'17" W	69.53'
L15	N 13°52'54" E	17.89'
L21	N 13°52'54" E	95.31'
L24	S 76°07'06" E	64.16

GENERAL NOTES:

1. THE PURPOSE OF THIS PLAT IS TO COMBINE TAX PARCELS 7.122.B.19 AND 7.122.B.19A AND TO RECOMBINE THESE TWO TAX PARCELS WITH 23,382 SF FROM LOT 2 OF (UNIVERSITY COMMONS). THIS MAP IS ALSO A BOUNDARY MAP OF TAX PARCEL 7.122.B.21 WHICH IS AN EXISTING LOT OF RECORD AND REMAINS UNCHANGED. THIS PLAT ALSO SHOWS EASEMENTS FOR PRIVATE ACCESS AND OWASA WATER AND SEWER EASEMENTS RECORDED ELESWHERE AS REFERENCED.
2. THIS PLAT DOES NOT REPRESENT A SUBDIVISION OF LAND. IT IS A RECOMBINATION AND EASEMENT MAP OF LOTS 1 AND 2 AND PARCEL "A" AND A BOUNDARY MAP OF PARCEL "B". FOR FURTHER INFORMATION SEE REFERENCES.
3. ZONING: RESIDENTIAL-10 IN CARRBORO; R-1 IN CHAPEL HILL.
4. THERE ARE NO NCGS MONUMENTS WITHIN 2000 FT. ALL DISTANCES SHOWN ARE IN HORIZONTAL DECIMAL FEET. AREA CALULATED BY COORDINATE GEOMETRY METHOD.
5. BUILDINGS SHOWN ARE PROPOSED AND THEIR LOCATIONS ARE APPROXIMATE.
6. BUILDING SETBACKS SHOWN ARE THOSE ON THE CONDITIONAL USE PERMIT AS APPROVED BY TOWN OF CARRBORO ON DECEMBER 17, 1996. THEY MAY BE SUBJECT TO CHANGE IN THE FUTURE BY AN OVERLAY ZONING DISTRICT OR OTHER REQUIREMENT OF THE TOWN OF CARRBORO.
7. PARCELS "A" AND "B" ARE LOCATED WITHIN A H.U.D.-DESIGNATED FLOOD HAZARD AREA OF MORGAN CREEK. PARCEL "B" IS LOCATED WITHIN THE TOWN OF CHAPEL HILL RCD (RESOURCE CONSERVATION DISTRICT), WHICH SERVERELY RESTRICTS DEVELOPMENT POTENTIAL.
8. THE TOWN LIMIT LINE BETWEEN CARRBORO AND CHAPEL HILL IS THE COMMON LINE BETWEEN PARCELS "A" AND "B". GROSS LAND AREAS ARE NOT FOR CONVEYANCE, BUT ARE FOR CHAPEL HILL DEVELOPMENT ORDINANCE PURPOSES.

#1=9778-71-7121.001 THRU 9778-71-7121.037
7.122H-1 7.122H-37

9778-71-8740 7.122.B.18B-Parent
9778-71-9635 7.122.B.18B #2
9778-81-1660 7.122.B.18B2 23,382SF
9778-81-1346 7.122.B.19 Parent
9778-81-2532 7.122.B.19A "
9778-81-2446 7.122.B.21A #B
9778-81-5524 7.122.B.21 Parent
9778-81-8578

PROPERTY OWNERS & SURVEYED AND MAPPED FOR:

ONSIGHT CORPORATION, LLC
P.O. BOX 27169
GREENVILLE, S.C. 29616

FOR UNIVERSITY COMMONS LOTS:
LOT 1
LOT 2

JOHN G. McCORMICK
976 AIRPORT ROAD
CHAPEL HILL, NC 27514

FOR TAX PARCELS:
7.122.B.19
7.122.B.19A

Certificate of Ownership and Dedication

ONSIGHT CORPORATION, L.L.C., a S.C. Limited Liability Company — 7/30/98

JOHN G. McCORMICK, Owner — 7/30/98

North Carolina, Chatham County

I, KELLY D. ARDOIN, a notary public for said county and state certify that SCOTT BRUNET, Manager of ONSIGHT CORPORATION, L.L.C., a South Carolina Limited Liability Company personally appeared before me this day and acknowledged the due execution of the foregoing instrument on behalf of the company.

Witness my official Seal, this 30th day of July, 1998

Kelly D. Ardoin, Notary Public — 10-22-2001 Commission Expires

North Carolina, Orange County

I, Kendra T. Dockery, a Notary Public for said County and State, do hereby certify that John G. McCormick personally appeared before me this day and acknowledged the due execution of the foregoing instrument. Witness my hand and official seal, this 30 day of August, 1998.

Notary Public Kendra T. Dockery
My commission expires 10/9/2002

AREA SUMMARY:

1. UNIVERSITY COMMONS – LOT ① = 8.662 AC.
LESS, AREA IN R/W(PB-78,PG-174)= -0.407 AC.
NET AREA ① = 8.255 AC.(UNCHANGED)

2. UNIVERSITY COMMONS – LOT ② = 8.499 AC
LESS, AREA IN R/W(PB-78,PG-174)= -0.228 AC.
LESS, RECOMBINATION PARCEL -0.537 AC. (THIS PLAT)
NET AREA ② = 7.734 AC.

3. McCORMICK – LOT Ⓐ = B.19A 55,657 SF
PLUS TAX PARCEL B.19 + 41,111 SF
PLUS, RECOMBINATION PARCEL 23,382 SF (0.537AC.)
NEW LOT Ⓐ AREA = 120,150 SF (2.758 AC.)

4. McCORMICK – LOT Ⓑ = 135,692 SF NET LAND AREA
PLUS +11,993 SF CREDITED OPEN SPACE (T of CH)
147,685 SF GROSS LAND AREA (T of CH)

State of North Carolina
County of Orange

I, Denise Y Robinson, Review Officer of Orange County, certify that the map or plat to which this certification is affixed meets all statutory requirements for recording for which the Review Officer has responsibility as provided by law.

Review Officer
Orange County Land Records/GIS

Date of Certification: 8-5-98

GRAPHIC SCALE
100 0 50 100 200 400
1 INCH = 100 FT.

RECORDED ORANGE COUNTY REGISTRY: BOOK 81, PAGE 72

PHILIP POST & ASSOCIATES
ENGINEERS PLANNERS SURVEYORS
401 Providence Road
Chapel Hill, NC 27514
(919)929-1173
493-2600 • 850-9662
822 North Elm Street
Greensboro, NC 27401
(919)273-7711

RECOMBINATION & BOUNDARY PLAT
UNIVERSITY COMMONS AND McCORMICK LANDS
TOWNS OF CARRBORO AND CHAPEL HILL
CHAPEL HILL TOWNSHIP ORANGE COUNTY, N.C.

SCALE 1" = 100'
DRAWN BY JAW
CHECKED BY PNF
DATE 7-30-98
PROJECT NO. 52702A
DRAWING NO. A722BP02

This drawing is the property of Philip Post and Associates Inc. and is not to be reproduced or copied in whole or in part. It is only to be used for the project and for the site specifically identified herein and is not to be used on any other project or site. It is to be returned upon the written request of Philip Post & Associates, Inc. COPYRIGHT 1998 Philip Post & Associates, Inc.

REVISIONS
1.) 5/29/98 AREA SUM. CHART

SHEET 1 OF 1